

TENDER NOTICE

OVERHEAD PROTECTION AT WAITING AREA OF ARMY PRE-PRIMARY SCHOOL VIJAY DURG

Dear Sir / Madam,

1. Army Pre Primary School Vijay Durg Kolkata intends to procure items for "**Overhead protection at waiting area of Army Pre-Primary School Vijay Durg**". Details of accoutrement are given below:-

<u>Ser No</u>	<u>Items/ Location</u>	<u>A/U</u>	<u>Area</u>	<u>Remarks</u>
1.1	Overhead protection at waiting area	Sqft	1850 (Approx)	Tech Specs at Appx A

2. **Two-Bid System for Procurement.** The bidding process shall follow a strict **Two-Bid System**, consisting of **Envelope 'A' (Technical Bid)** and **Envelope 'B' (Financial Bid)**. Both envelopes must be sealed separately, super-scribed with the tender reference number, project name ("**Overhead protection at waiting area of Army Pre-Primary School Vijay Durg**"), and the type of bid. Both individual envelopes must then be enclosed together within a single, larger outer sealed envelope addressed to the School Procurement Committee. Details of Technical Specification and commercial bid of Items are attached as **Appendix A and B**.


3. Please drop sealed quotation in Quotation Box kept in Army Pre Primary School Vijay Durg, Kolkata – 700021 or send it by Registered Post before due date to under mentioned address - **Army Pre-Primary School Vijay Durg, Kolkata-700021 (South Gate), Army Camp (Fort William), Contact Number: 7487038274**.

4. **Site Visit.** The bidder, at their own responsibility may to visit and examine the site and its surroundings at their own expense. Site visits must be conducted strictly from Monday to Friday, during working hours between 08:30 and 14:30 hrs. The bidder is responsible for obtaining all necessary information required to prepare the bid and enter into a contract for the services. Additionally, the vendor **must submit a detailed engineering drawing and an architectural design** of the shed as part of their proposal.

5. Registered interested vendors who have GST No are invited to visit venue and submit sealed proposal is two envelopes marked as Technical Bid and commercial Bid of above items by **12 Oct 2026** positively. The vendors are requested to submit Bid alongwith **copy of GST registration Certificate, Firm registrations & copy of PAN Card** by due date.

6. Quotation will be opened on **13 Oct 2026** at 1030hrs, Incomplete and late submission of quotation will not be entertained. All vendors (who have submitted the Quotation) or their representatives are requested to be present at Army Pre Primary School Vijay Durg, Kolkata during opening of quotations. Only the technical bids will be opened on the tender opening day.

7. **Inspection and Quality Control.** The Purchaser reserves the right to inspect items at the Supplier's facility prior to dispatch. Any items found damaged, defective, or not conforming to the technical specifications upon arrival will be rejected at the Supplier's cost. Rejected items must be sent within 7 days.



8. Delivery of Items.

8.1 Delivery Site / Destination. The Seller shall deliver all items ordered under this Supply Order to the following exact physical address: Army Pre-Primary School Vijay Durg, Kolkata-700021 (South Gate), Army Camp (Fort William), Contact Number: 7487038274.

8.2 Time of Essence & Deadline. Delivery & installation of stores would be completed within **45 days** from the elective date of SO. Please note that SO can be cancelled unilaterally by the Buyer in case the stores is not supplied & installed within the stipulated period. Extension of delivery period will be at the sole discretion of the Buyer and will incur an LD (Liquid Damages) @ 0.5% of the cost of every week of delay and part thereof.

9. Warranty. All supplied items are backed by a comprehensive, all-inclusive, on-site warranty for a minimum period of **5 Years**. The warranty coverage shall formally commence from the exact date of final quality inspection acceptance and operational sign-off by the Buyer. Under this warranty, the Seller must repair or replace any defective components on-site within **5 days** of receiving a written defect notice, at zero additional cost to the Buyer.

File No: 141124/Sigs/ADM/26-27/APPSVD




प्रधानाचार्य
Principal
(Mrs. Anuradha Vijay Durg)
Army Pre-Primary School, Vijay Durg
वियज दुर्ग, कोलकाता-२१
Vijay Durg, Kolkata-21

**TECHNICAL SPECIFICATION OF ITEMS FOR THE PROJECT "OVERHEAD
PROTECTION AT WAITING AREA OF ARMY PRE-PRIMARY
SCHOOL VIJAY DURG"**

<u>Ser No</u>	<u>Technical Specification</u>		<u>Make & Model</u> <u>(Where ever applicable)</u>	<u>Complied (Yes/ No)</u>
1.	Description	Specification		
	Total area covered	Approx 1850 sqft (Approx)		
	Material Used for structure	Mild Steel		
	Clear Height of the structure	10.5 Ft		
	Roof top material	Polycarbonate sheet		
	Steel quantity for structure	2,800 Kg		
	Total polycarbonate sheet area	2250 sqft		
	Fabricated steel frame – base coat	1 coat Red oxide		
	Fabrication steel frame – top coat	2 coat enamel paint		
2.	Civil & Foundation work			
	2.1 Marking of column locations as per layout/drawing.			
	2.2 Setting out of foundation locations and levels.			
	2.3 Any adjustment required due to actual site conditions shall be mutually discussed and approved before execution.			
	2.4 Earth Cutting for individual column foundations of approximately 220 mm × 220 mm along with supply and installation of 12 mm reinforcement bars as required for foundation support, casting of foundation using cement concrete			
	2.5 Adequate curing of concrete after casting.			
	2.6 Supply and installation of MS foundation bolt 16 mm& MS Base plate 12 mm for supporting the MS columns.			
3.	MS Structure & Fabrication.			
	3.1 Supply of MS structure material as mentioned in the material list.			
	3.2 On site Fabrication of columns and truss along with erection of the structure.			
	3.3 Supply and fitting of Polycarbonate sheet for overhead roof.			



<u>Ser No</u>	<u>Technical Specification</u>	<u>Make & Model</u> <u>(Where ever applicable)</u>	<u>Complied</u> <u>(Yes/ No)</u>
	3.4 Supply of all accessories and consumable e for proper welding, alignment and fitting of the MS material and polycarbonate sheet.		
	3.5 Application of 1 coat red oxide and 2 coat final enamel paint on the MS structure		
4.	Material to be used for structure work.		
	4.1 Hollow pipe 100X100 mm of 4 mm thickness		
	4.2 Hollow pipe 50X50 mm of 3.2 mm thickness		
	4.3 Hollow pipe 50X50 mm of 2.9 mm thickness		
	4.4 Hollow pipe 38X38 mm of 2.6 mm thickness		
	4.5 MS plate 12 mm thickness		
	4.6 Foundation Bolt 16 mm		
	4.7 Polycarbonate sheet 2 mm thickness		
5.	Drain. Provision of perimeter drainage on one side of the structure to act as attached gutters along the edge of the shed roof to catch facing rain and guide water safely down the roof.		
6.	Bidders shall submit a valid structural stability/ safety certificate for the said from a qualified Architecture/ Civil Engineer.		
7.	Vendor to submit a detailed engineering drawing and architectural design of the shed.		



**COMMERCIAL BID FOR THE PROJECT "OVERHEAD PROTECTION AT WAITING
AREA OF ARMY PRE-PRIMARY SCHOOL VIJAY DURG**

Ser No	Items	A/U	Qty	Unit Cost	Tax	Total Cost
1.1	Overhead protection at waiting area	Sqft	1850 (Approx)			

